Maintenance Agreement

This agreement covers the maintenance of heating, ventilation and air-conditioning equipment in the three buildings listed in Schedule A. The contractor will keep a written log of every visit and share it with the facilities manager within two working days.

Routine inspections take place every quarter. During each inspection the technician checks filters, belts, thermostats and condensate drains, replaces worn parts from the agreed stock list and records meter readings for the energy report.

Emergency call-outs are answered around the clock. A qualified engineer must arrive on site within four hours of the call for critical faults, and within one business day for everything else. Response times are measured from the moment the ticket is logged.

Spare parts that are not on the stock list are ordered only after written approval. The contractor will provide two quotations for any single part costing more than the approval threshold and will keep removed parts for inspection for thirty days.

Safety comes first. Technicians wear the protective equipment required by the site rules, follow lock-out procedures before opening any electrical panel and report near misses to the site safety officer on the same day.

Each month the contractor sends a short report that lists completed jobs, open tickets, parts used and the energy consumption of the main plant. Charts in the report compare the current month with the same month of the previous year.

Access to the buildings is arranged through the reception desk. Visitors sign in, receive a temporary badge and are accompanied in plant rooms. Keys to the roof must be returned before the end of the working day.

Waste refrigerant, used oil and old filters are collected separately and handed to a licensed disposal company. Transfer notes are kept for three years and copies are attached to the quarterly report.