Maintenance Agreement

This agreement covers the maintenance of heating, ventilation and air-conditioning equipment in the three buildings listed in Schedule A. The contractor will keep a written log of every visit and share it with the facilities manager within two working days.

Routine inspections take place every quarter. During each inspection the technician checks filters, belts, thermostats and condensate drains, replaces worn parts from the agreed stock list and records meter readings for the energy report.

Emergency call-outs are answered around the clock. A qualified engineer must arrive on site within four hours of the call for critical faults, and within one business day for everything else. Response times are measured from the moment the ticket is logged.

APPROVED

Spare parts that are not on the stock list are ordered only after written approval. The contractor will provide two quotations for any single part costing more than the approval threshold and will keep removed parts for inspection for thirty days.

Safety comes first. Technicians wear the protective equipment required by the site rules, follow lock-out procedures before opening any electrical panel and report near misses to the site safety officer on the same day.