Meter reading routine (synthetic sample)

Carry out these steps each morning:

1. Open the control cabinet.
2. Check the indicator lamps.
3. Wear insulated gloves.
4. Test the gloves for holes.
5. Check the floor mat is dry.
6. Tell the control room you are starting.
7. Read the meter.
8. Note the reading in the log.
9. Close the cabinet.
10. Sign the log.

Report any fault to the duty engineer.